CAUTION: IF THIS SHEET IS NOT 30"x42" IT IS A REDUCED PRINT



1 ONE LINE DIAGRAM - (1F0) ELECTRODE "B" (PARTIAL)

NO SCALE

BUS DUCT NAME

1F0EL-BD-B-01A

BUS PLUG EQUIPMENT	TAG #	VOLTS	AMP FRAME	AMP TRIP	LOAD	DEM	DEM LOAD	FLA	NOTES
		RATINGS			LOADING (KVA)				
INVERTER PANEL	1	480	600	500	377	0.4	151	453	
CONTROL/DRIVE PANEL	2	480	150	40	22	0.4	9	27	
INVERTER PANEL	3	480	600	500	377	0.4	151	453	
CONTROL/DRIVE PANEL	4	480	150	40	22	0.4	9	27	
INVERTER PANEL	5	480	600	500	377	0.4	151	453	
CONTROL/DRIVE PANEL	6	480	150	40	22	0.4	9	27	
INVERTER PANEL	7	480	600	500	377	0.4	151	453	
CONTROL/DRIVE PANEL	8	480	150	40	22	0.4	9	27	FUTURE
INVERTER PANEL	9	480	600	500	377	0.4	151	453	FUTURE
CONTROL/DRIVE PANEL	10	480	150	40	22	0.4	9	27	FUTURE
INVERTER PANEL	11	480	600	500	377	0.4	151	453	FUTURE
CONTROL/DRIVE PANEL	12	480	150	40	22	0.4	9	27	FUTURE
INVERTER PANEL	13	480	600	500	377	0.4	151	453	FUTURE
CONTROL/DRIVE PANEL	14	480	150	40	22	0.4	9	27	FUTURE
INVERTER PANEL	15	480	600	500	377	0.4	151	453	FUTURE
CONTROL/DRIVE PANEL	16	480	150	40	22	0.4	9	27	FUTURE
1F0EL-HPP-1 01	17	480	400	250	15	1.0	15	18	
CONTROL/DRIVE PANEL	18	480	150	40	22	0.4	9	27	
CONTROL/DRIVE PANEL	19	480	150	40	22	0.4	9	27	
CONTROL/DRIVE PANEL	20	480	150	40	22	0.4	9	27	
CONTROL/DRIVE PANEL	21	480	150	40	22	0.4	9	27	
CONTROL/DRIVE PANEL	22	480	150	40	22	0.4	9	27	
CONTROL/DRIVE PANEL	23	480	150	40	22	0.4	9	27	
CONTROL/DRIVE PANEL	24	480	150	40	22	0.4	9	27	
ANODE(-) MAIN PANEL CHILLER #12	25	480	250	250	182	0.4	73	219	
ANODE(-) R2R DRYER MAIN PANEL #12	26	480	400	400	253	0.4	101	304	

NOTES:
*800A AND ABOVE BUS PLUGS REQUIRE MANUFACTURER INSTALLED BUS PLATE. SEE POWER PLAN FOR LOCATION

TOTAL LOAD (KVA) 3800

1529 TOTAL DEMAND LOAD (KVA)
1839.04 DEMAND AMPS
2500 RATING (A)
74 % LOADING

BUS DUCT NAME

1F0EL-BD-B-01B

BUS PLUG EQUIPMENT	TAG #	VOLTS	AMP FRAME	AMP TRIP	LOAD	DEM	DEM LOAD	FLA	NOTES
		RATINGS			LOADING (KVA)				
ANODE(-) MAIN PANEL CHILLER #1	1	480	250	250	182	0.4	73	219	
ANODE(-) R2R DRYER MAIN PANEL #1	2	480	400	400	253	0.4	101	304	
ANODE(-) MAIN PANEL CHILLER #2	3	480	250	250	182	0.4	73	219	
ANODE(-) R2R DRYER MAIN PANEL #2	4	480	400	400	253	0.4	101	304	
ANODE(-) MAIN PANEL CHILLER #3	5	480	250	250	182	0.4	73	219	
ANODE(-) R2R DRYER MAIN PANEL #3	6	480	400	400	253	0.4	101	304	
ANODE(-) MAIN PANEL CHILLER #4	7	480	250	250	182	0.4	73	219	
ANODE(-) R2R DRYER MAIN PANEL #4	8	480	400	400	253	0.4	101	304	
ANODE(-) MAIN PANEL CHILLER #5	9	480	250	250	182	0.4	73	219	
ANODE(-) R2R DRYER MAIN PANEL #5	10	480	400	400	253	0.4	101	304	
ANODE(-) MAIN PANEL CHILLER #6	11	480	250	250	182	0.4	73	219	
ANODE(-) R2R DRYER MAIN PANEL #6	12	480	400	400	253	0.4	101	304	
ANODE(-) MAIN PANEL CHILLER #7	13	480	250	250	182	0.4	73	219	
ANODE(-) R2R DRYER MAIN PANEL #7	14	480	400	400	253	0.4	101	304	
ANODE(-) MAIN PANEL CHILLER #8	15	480	250	250	182	0.4	73	219	
ANODE(-) R2R DRYER MAIN PANEL #8	16	480	400	400	253	0.4	101	304	
ANODE(-) MAIN PANEL CHILLER #9	17	480	250	250	182	0.4	73	219	
ANODE(-) R2R DRYER MAIN PANEL #9	18	480	400	400	253	0.4	101	304	
ANODE(-) MAIN PANEL CHILLER #10	19	480	250	250	182	0.4	73	219	
ANODE(-) R2R DRYER MAIN PANEL #10	20	480	400	400	253	0.4	101	304	
ANODE(-) MAIN PANEL CHILLER #11	21	480	250	250	182	0.4	73	219	
ANODE(-) R2R DRYER MAIN PANEL #11	22	480	400	400	253	0.4	101	304	
1F0EL-HPP-1 02	25	480	400	250	61	1.0	61	74	

NOTES:
*800A AND ABOVE BUS PLUGS REQUIRE MANUFACTURER INSTALLED BUS PLATE. SEE POWER PLAN FOR LOCATION

TOTAL LOAD (KVA) 4847

1976 TOTAL DEMAND LOAD (KVA)
2376.57 DEMAND AMPS
2500 RATING (A)
95 % LOADING

3 BUS DUCT LOAD SCHEDULE

NO SCALE



2 EQUIPMENT ELEVATION

NO SCALE

GENERAL NOTES

A. REFERENCE FEEDER SCHEDULE, E011

B. CABLE LENGTHS WHEN INDICATED ON ONE-LINE ARE APPROXIMATE AND ARE FOR REFERENCE ONLY FOR CALCULATIONS AND ARE NOT TO BE USED FOR MATERIAL TAKEOFFS.

C. SECONDARY UNIT SUBSTATIONS: REFER TO SPECIFICATION #26 11 16 12.

D. UNIT SUBSTATION SCADA COMMUNICATIONS SHALL INCLUDE ALL HARDWARE DEVICES TO COMMUNICATE I/O (VIA MODBUS TCP COMMUNICATIONS) INCLUDING, BUT NOT LIMITED TO, THE FOLLOWING:

PRIMARY SWITCH STATUS (OPEN/CLOSED)
TRANSFORMER WINDING TEMPERATURE
TRANSFORMER FAN RUN STATUS
BREAKER STATUS
POWER METER DATA

E. ALL SWITCHBOARDS, SWITCHGEAR, AND PANELBOARDS SUPPLIED BY FEEDERS SHALL BE PERMANENTLY MARKED TO INDICATE EACH DEVICE OR EQUIPMENT WHERE THE POWER ORIGINATES. THE LABEL SHALL BE PERMANENTLY AFFIXED, OF SUFFICIENT DURABILITY TO WITHSTAND THE ENVIRONMENT INVOLVED, AND NOT HANDWRITTEN.

KEYED NOTES

1. NOT USED
2. PRIOR TO CLOSING A SWITCH, THE OTHER SWITCH MUST BE OPENED USING KIRK KEY INTERLOCK TO PREVENT CONNECTION OF MULTIPLE SOURCES. REFER TO SEQUENCE OF OPERATIONS BY MANUFACTURER IN EQUIPMENT SUBMITTAL.
3. NOT USED.
4. SQUARE D/ SCHNEIDER ION 9000 WITH RS-485 COMMUNICATIONS.
5. ENGINEERED CABLE BUS ASSEMBLY, CONDUIT, OR CABLE TRAY TO BUS DUCT CABLE TAP BOX.

WARE MALCOMB
ARCHITECTURE CIVIL ENGINEERING
PLANNING BRANDING
INTERIORS BUILDING MEASUREMENT
2777 E. Camelback Rd. Suite #325
Phoenix, AZ 85016
P 480.907.2288

10/23/25
30536
WILLIAM J. BETHURUM, IV
SEAL EXPIRES: 09/30/26

VOLTA
1730 E. Northern Avenue, Ste. 120, Phoenix, AZ 85020
Tel. (480) 899-0511, VoltaUS.com
VUS 215101 10.23.25

PROJECT ALPHA

1F0 - MAIN MANUFACTURING BUILDING
EAST PECOS ROAD
QUEEN CREEK, ARIZONA 85140

ELECTRICAL ONE LINE DIAGRAM

DATE	REMARKS
10/16/2024	IDC-074 1F0 CD PROGRESS SET (MEP ONLY)
11/01/2024	IDC-074 1F0 FULL CD PACKAGE
12/17/2024	1F0 IDC-074 REVISIONS
03/11/2025	1F0 CD REVISIONS
06/19/2025	1F0 CD REISSUANCE
07/24/2025	1F0 CD PERMIT RESUBMISSION
10/23/2025	1F0 BULLETIN #1

PA/PM:	WB
DRAWN BY.:	ETS/AO/IA/JG
JOB NO.:	PHX21-5038-00

SHEET

1F0-E607

PLOT DATE: 10/23/2025

G:\Shared drives\projects\22\1F1\215101\215101A2_1lines.dwg