

STRUCTURE CIVIL ENGINEERING
FIG BRANDING
PS BUILDING MEASUREMENTS

[illegible]

PROJECT ALPHA
1F0 - MAIN MANUFACTURING BUILDING
EAST PECOS ROAD
QUEEN CREEK, ARIZONA 85140

EMERGENCY GENERATOR ONE LINE DIAGRAM

DATE	REVISIONS	REMARKS
06/26/2024	FIG. 2-170 REVISIONS	
06/26/2024	PERMIT RESUBMISSION 623-1400	
10/16/2024	DOC-074 FID PROGRESS SET (MEP ONLY)	
12/17/2024	FIG. 100-174 REVISIONS	
12/17/2024	FIG. 100-174 REVISIONS	
03/11/2025	FIG. 03 REVISIONS	
10/23/2025	FID BUILDING #1	

PA/PM:	WB
DRAWN BY.:	ETS/AO/IA/JG
JOB NO.:	PHX21-5038-00

SHEET

1F0-E601

KEYED NOTES

- A. REFERENCE FEEDER SCHEDULE, E011
 - B. THE FACTORY BUILDING (EXCLUDING ELECTRICAL ROOMS) IS EQUIPPED WITH AN AUTOMATIC FIRE SUPPRESSION SYSTEM.
 - C. ALL SWITCHBOARDS, SWITCHGEAR, AND PANELBOARDS SUPPLIED BY FEEDERS SHALL BE PERMANENTLY MARKED TO INDICATE EACH DEVICE OR EQUIPMENT WHERE THE POWER ORIGINATES. THE LABEL SHALL BE PERMANENTLY AFFIXED, OF SUFFICIENT DURABILITY TO WITHSTAND THE ENVIRONMENT INVOLVED, AND NOT HANDWRITTEN
- ## KEYED NOTES ○
1. GROUND FAULT, ALARM ONLY, WHERE INDICATED
 2. LOCATE REMOTE GENERATOR ANNUNCIATION PANEL (RAP) IN NEAREST ELECTRICAL ROOM UNLESS DIRECTED OTHERWISE BY OWNERSHIP. PROVIDE, CONDUIT PER SITE PLAN (1FG-E100) AND CABLEING PER MANUFACTURER RECOMMENDATION
 3. PROVIDE (2) 1-1/2" C FOR CONTROL WIRING. PROVIDE (1) 2" C. FOR GENERATOR PANEL
 4. PROVIDE DOCKING STATION WITH KIRK-KEY REMOVED. CALL OUTED CABLEING TO TEMPORARY GENERATOR AND LOAD BANK.

KEYED NOTES

1. GROUND FAULT, ALARM ONLY, WHERE INDICATED
2. LOCATE REMOTE GENERATOR ANNUNCIATION PANEL (RAP) IN NEAREST ELECTRICAL ROOM UNLESS DIRECTED OTHERWISE BY OWNERSHIP. PROVIDE CONDUIT PER SITE PLAN (1FO-E100) AND CABLEING PER MANUFACTURER RECOMMENDATION.
3. PROVIDE (2) 1-1/2" C FOR CONTROL WIRING. PROVIDE (1) 2" C. FOR GENERATOR PANEL.
4. PROVIDE DOCKING STATION WITH KIRK-KEY INTERLOCKED CAM-LOCKS FOR CONNECTION TO TEMPORARY GENERATOR AND LOAD BANK.

